BRUHAT BANGALORE MAHANAGAR PALIKE

Project Division, Yelahanka Zone

SCHEDULE - B

Providing and Installation of Water fountains in Ward No.10 Doddabommasandra

SNo	Quantity	Item Name	Unit	Approved Rates of M/s Color Desgin India	
				In figures	In words
1	61.28	KSRRB 300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications (PWD SR 2018-19, I No-19.1, P No-143)	Cum	353.00	Rupees Three Hundred Fifty Three Only
2	0.89	KSRB 2.6 : Providing and filling sand in foundation to required depth for sub soil treatment including watering ramming with all lead and lift complete as per specifications. (PWD SR 2018-19 It No. 2.13 Pg. No.7)	Cum	5250.00	Rupees Five Thousand Two Hundred Fifty Only
3	1.79	KSRB 4-1.4 : Providing and laying in position plain cement concrete of Mix 1:5:10 with OPC @ 160kgs, with 40mm and down size graded granite metal coarse aggregates @0.86cum and fine aggregtes @ 0.58cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM curing complete as per specifications. (PWD SR 2018-19 It No.4.4 Pg. No.13)	Cum	6220.00	Rupees Six Thousand Two Hundred Twenty Only
4	1.61	KSRB 4-1.6 ; Providing and laying in position plain cement concrete of Mix 1:2:4 with OPC @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregtes @ 0.53cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing complete as per specifications. Specification No. KBS 4.1, 4.2 (PWD SR 2018-19 It No.4.6 Pg. No.13)	Cum	7680.00	Rupees Seven Thousand Six Hundred Eighty Only
5	32.38	KSRB 6-2 : Providing and constructing burnt brick masonry with approved quality of non-modular bricks of standard size of class designation 5.0Newton per sqmm (table moulded) with cement mortar 1:6 for basement and superstructu/re including cost of materials, labour charges, scaffolding, curing complete as per specifications. (PWD SR 2018-19 It No.6.6 Pg. No.29)	Cum	6200.00	Rupees Six Thousand Two Hundred Only
6	32.38	KSRB15-3 : Providing 15mm thick cement plaster in single coat with cement mortar to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. PWD SR 2018-19 It No. 15.13 Pg. No.115, cement mortar 1:4	Sqm	325.00	Rupees Three Hundred Twenty Five Only
7	59.64	KSRB 14.14-5: Providing Ceramic tiles of approved make,shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment , including cost of materials, labour, curing, complete as per specifications. Specification No. KBS for Ceramic Tiles of size 15x15cms 6mm thick (PWD SR 2018-19 It No.14.36.1 Pg. No.108)	Sqm	1830.00	Rupees One Thousand Eight Hundred Thirty Only
8	7.77	KSRB 14.4 : Providing and laying flooring and steps fine dressed granite stone slabs 40 mm thick on cement mortar bed 1:6, 25 mm thick, and pointed with cement mortar 1:3 over existing cement concrete bed, including cost of materials, mortar, labour, curing complete as per specifications. (PWD SR 2018-19 It No.14.4 Pg. No.103)	Cum	12250.00	Rupees Twelve Thousand Two Hundred Fifty Only

For COLOR DESIGN INDIA

Contractor

Auth.Sign.

Executive Engineer
Project Division
Yelahanka Zone

	Quantity	Item Name	Unit	Approved Rates of M/s Color Desgin India	
				In figures	In words
	1.80	Providing half nosing for 40mm thick granite slab using required machinery including cost and conveyance of all materials, labour for all items of work, HOM etc., complete as per specification (PWD SR 2018-19 It No.14.54 Pg. No.111)	m	550.00	Rupees Five Hundred Fifty Only
10	25.90	KSRRB M300-53. Construction of embankment with approved material Gravel/Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications, including cost of gravel / murrum, watering charges & compaction by vibratory roller to 95% of modified proctors density. (PWD SR 2018-19 It No.19.60 Pg. No.147)	Cum	1246.00	Rupees One Thousand Two Hundred Forty Six Only
11	77.70	KSRRB M300- 2.1. Grassing with Doobs grass including watering and maintenance of the lawn for 30 days or more till the grass forms a thick lawn free from weeds and fit for moving including supplying good earth if needed complete as per specifications. (PWD SR 2018-19 It No.19.78 Pg. No.148)	Sqm	920.00	Rupees Nine Hundred Twenty Only
12	1.00	A. Design, Supply, Installation, Testing & Commissioning of Dancing Traditional Ring Fountain with Foam Jets consists of 12 feet & 4 feet diameter circular spray rings each 1 no. made up of 2" dia stainless steel 304 grade pipes with necessary inlets & 100 nos. coupling welded for nozzles fixing including necessary support legs to fix the ring on the wall, B. 5 H.P Openwell submersible monoblock water-cooled pump 1 no. (Three phase – 2880 Rpm – 440 V – 50 Hz Suguna or CRI make or Texmo make) made up of high grade cast iron materials, C. Angle adjustable smooth stream nozzles 100 nos. made up of brass with nickel plating, D. Multi color 18 Watts – 12 Volts L.E.D lights 24 nos. made up of stainless steel, sealed with heat resistant, toughened glass provided with stainless steel mounting cradle, E. Supreme make ASTM D1785 SCH 40 UPVC pipes, ASTM D2467 SCH 80 UPVC fittings & control valves, F. Solenoid Valves 5 nos. for dancing effectsG. Sequential control unit consists of preprogrammed and automatic ON – OFF for dancing effects, necessary wire mesh unit made up of stainless steel with stainless steel frame for protect the pump from the dust and garbage articles and necessary electrical items like Control Panel made up of 16 SWG powder coated mild steel including BCH / L&T make panel board for 3 H.P pump consisting of isolated switch, phase lights, start and stop push buttons, contactor, relay, volt meter, ammeter in a powder coated mild steel enclosures, 40 Amps 4 pole Legrand / L&T make isolator, 20 amps single pole Legrand / L&T make miniature circuit breaker, necessary 1.0 Sq.mm 4 core Havels / Polygon / Finolex make electric cables for lights, automatic colour changing ON-OFF timer control 1 no. for lights with powder coated mild steel control panel 1 no, H. Professional charges for fountain erection etc. complete. (Approved data rate) 12' dia = 3.7m	Unit	1235000.00	Rupees Twelve Lakh(s) Thirty Five Thousand Only

For COLOR DESIGN INDIA

Auth.Sign.

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Quantity	Item Name	Unit	Approved Rates of M/s Color Desgin India	
				In figures	In words
13	1.00	A. Design, Supply, Installation, Testing & Commissioning of Dancing Traditional Ring Fountain with Foam Jets consists of 15 feet & 4 feet diameter circular spray rings each 1 no. made up of 2" dia stainless steel 304 grade pipes with necessary inlets & 100 nos. coupling welded for nozzles fixing including necessary support legs to fix the ring on the wall, B. 5 H.P Openwell submersible monoblock water-cooled pump 1 no. (Three phase – 2880 Rpm – 440 V – 50 Hz Suguna or CRI make or Texmo make) made up of high grade cast iron materials, C. Angle adjustable smooth stream nozzles 100 nos. made up of brass with nickel plating, D. Multi color 18 Watts – 12 Volts L.E.D lights 24 nos. made up of stainless steel, sealed with heat resistant, toughened glass provided with stainless steel mounting cradle, E. Supreme make ASTM D1785 SCH 40 UPVC pipes, ASTM D2467 SCH 80 UPVC fittings & control valves, F. Solenoid Valves 5 nos. for dancing effectsG. Sequential control unit consists of preprogrammed and automatic ON – OFF for dancing effects, necessary wire mesh unit made up of stainless steel with stainless steel frame for protect the pump from the dust and garbage articles and necessary electrical items like Control Panel made up of 16 SWG powder coated mild steel including BCH / L&T make panel board for 3 H.P pump consisting of isolated switch, phase lights, start and stop push buttons, contactor, relay, volt meter, ammeter in a powder coated mild steel enclosures, 40 Amps 4 pole Legrand / L&T make isolator, 20 amps single pole Legrand / L&T make miniature circuit breaker, necessary 1.0 Sq.mm 4 core Havels / Polygon / Finolex make electric cables for lights, automatic colour changing ON-OFF timer control 1 no. for lights with powder coated mild steel control panel 1 no, H. Professional charges for fountain erection etc. complete. (Approved data rate) 15' dia = 4.6m	Unit	1325500.00	Rupees Thirteen Lakh(s) Twenty Five Thousand Five Hundred Only
14		GST @ 12% (For SR 2018-19 Items Only)			

For COLOR DESIGN INDIA

Contractor

Auth.Sign.

Executive Engineer
Project Division
Yelahanka Zone